ORDER WILL NOT BE RELEASED FOR FABRICATION UNTIL SIGNED COPY IS RECEIVED.

VERIFICATION AND APPROVAL OF GENERAL ARRANGEMENT AND OVERALL DIMENSIONS FOR THIS DOCUMENT ARE REQUIRED BEFORE THE ORDER IS ENTERED FOR MANUFACTURING.

APPROVAL SIGNATURE _____

TITLE HELD _____

DATE OF APPROVAL _____





ISOMETRIC VIEW





SECTION A-A

NOTES:

SIZE: 2'-6" X 8'-0"

1. CURB MATERIALS
   a. 0.090 ALUMINUM CURB
2. CURB CAP MATERIALS
   b. 0.090 ALUMINUM CURB CAP
3. CURB INSULATION THICKNESS AND MATERIALS
   c. 1" RIGID FIBERBOARD CURB INSULATION
4. COVER MATERIALS
   d. 0.090 ALUMINUM COVER
5. COVER LINER MATERIALS
   e. 0.063 ALUMINUM COVER LINER
6. COVER INSULATION THICKNESS AND MATERIALS
   f. 1" FIBERGLASS COVER INSULATION
7. COVER RATED FOR 40PSF LIVE LOAD
8. COVER AND CURB ARE MILL FINISH
9. ZINC PLATED HARDWARE

DRAWN BC	4/5/2019	HART & COOLEY INC. Fax: 855-549-2674 www.hartandcooleyinc.com 5030 Corporate Exchange Blvd. SE Grand Rapids, MI. 49512 Ph: 800-624-8642
CHECKED CD	MILCOR	
QA	TOLERANCE UNLESS SPECIFIED	TITLE: RD-3 30"X96" SINGLE LEAF ROOF HATCH
MFG	.XXX ± 0.005"	
APPROVED	.XX ± 0.01"	
	FRACT. ± 1/16"	SIZE D · DWG NO 3501-138-9 · REV A
	ANGLES ± 1˚	SCALE · SHEET 1 OF 1